



195 AVENUE RECONSTRUCTION

March 16, 2016



195 AVENUE RECONSTRUCTION

About the Project

The City of Edmonton is reconstructing 195 Avenue from 17 Street NE to the Horsehills Creek beginning in May 2016.

Construction includes:

- Complete removal and reconstruction of the roadway
- Widening of the roadway by 2 metres to bring it up to a rural standard—9m final width with 3.5m lanes and 1.0m shoulders
- Replacement of culverts
- Access approach reconstruction
- Grading of ditches, where required
- Brush clearing (within road right-of-way)
- Re-establishment of landscaping by placement of topsoil and seed in disturbed areas

Construction Sequencing

Construction begins May 2016, with completion in Fall 2016.

- Traffic will be restricted to local traffic only during construction
- Local accesses will be provided during construction

- Accesses will be closed during reconstruction of the access and adjacent roadway
- The accesses will be re-established promptly with a gravel surface
- Staged total closures will be used for asphalt paving

Drainage

Existing ditches will be re-established to ensure safe side slopes.

Road drainage will remain in the right-of-way, where possible.

Existing drainage patterns will be maintained, to ensure changes to the roadway do not create new drainage issues or flooding on private property.

Environment

The City of Edmonton's Forestry group will conduct brush removal and pruning in late March/April. Trees on private property overhanging the roadway will be pruned, as required.

The City has identified a Class IV wetland near the West limit of the project. Approvals are being pursued with Alberta Environment and Parks. Disturbance will be limited to the road right-of-way.

For More Information

Edmonton.ca/195avenue